

EMPIRE WORKROOM

CUSTOM UPHOLSTERY & FABRICATION
5124 Frolich Ln, Hyattsville, MD 20781
(703) 213-6484 | workroom@empirebox.store

ESTIMATE

No. EST-2026-110
Date: July 13, 2026
Valid: 30 days

PREPARED FOR

Maggie O'Neil

Material: caramel faux leather

PROJECT SITE

The Willard Hotel, Washington, DC

Priority: RUSH

#	DESCRIPTION	AMOUNT
1	Curved Upholstered Bench with Left Armrest Bench: 87" wide along back curve × 26" deep × 17" high; concave curve to wall, fully upholstered in caramel faux leather; six custom square exposed wood legs (6" max). Armrest (left, facing): independent piece, 4" W × 26" D, follows the curve, spans 6"–24" AFF (top 7" above seat). Overall assembly 91" along back curve.	\$1,933.33
2	Upholstered Channel Wall Panel 87" W × 24" H, wall-mounted behind bench in caramel faux leather. Eight vertical channels @ 10-49/64" W × 24" H with 1/8" reveals (8 × 10-49/64" + 7 × 1/8" = 87" exact — flush both ends). Panel bottom aligned to seat line at 17" AFF; combined height ~41" AFF.	\$966.67
Total		\$2,900.00
Deposit to begin (50%)		\$1,450.00
Balance on completion		\$1,450.00

NOTES

Shop drawings (2 sheets) and design concept rendering accompany this estimate.
Field verification of wall curvature at The Willard required prior to fabrication;
final curve radius, leg cross-section, and panel mounting height to be confirmed at site visit.
Estimate covers fabrication and materials; delivery and installation quoted separately if required.